CUSTOMER :

JOB NAME : THE STANDARD AT FORT COLLINS

LOCATION :

DESCRIPTION : WALL FOOTING (PARKING) NORTH BUILDING 1

DRAWING NO : RWF-01 THRU RWF-16

REVISION NO : 0

DATE :

CONCRETE REQUIREMENTS

Element Name	Part Mark	QTY.	Dimension (Ft-In)			CONCRETE PSI	AGGREGATE SIZE	REQUIRED SLUMP	REQUIRED AIR	REQUIRED W/C RATIO	REQUIRED (Cu-Yard)
			Length	Width	Height						
SW FOOTING	SWF1	1	17-06	3-00	35-09 1/8	4000.0000	1" minus	4.0000	1.5%	0.5500	69.53
	SWF2	1	26-09	4-02	56-08 15/16	4000.0000	1" minus	4.0000	1.5%	0.5500	234.26
WALL FOOTING	SWF3	2	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	257.29
	WF1	3	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	35.05
	WF10	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	21.09
	WF11	1	10-03	1-11	30-00	4000.0000	1" minus	4.0000	1.5%	0.5500	21.83
	WF11,WF12	1	10-03	3-06	4-00	4000.0000	1" minus	4.0000	1.5%	0.5500	5.31
	WF12	1	10-03	2-06	20-09 15/16	4000.0000	1" minus	4.0000	1.5%	0.5500	19.77
	WF12,WF13	1	10-03	4-09	4-00	4000.0000	1" minus	4.0000	1.5%	0.5500	7.21

Total:

											671.34

CUSTOMER :

JOB NAME : THE STANDARD AT FORT COLLINS

LOCATION :

DESCRIPTION : WALL FOOTING (PARKING) NORTH BUILDING 1

DRAWING NO : RWF-01 THRU RWF-16

REVISION NO : 0

DATE :

CONCRETE REQUIREMENTS

Element Name	Part Mark	QTY.	Dimension (Ft-In)			CONCRETE PSI	AGGREGATE SIZE	REQUIRED SLUMP	REQUIRED AIR	REQUIRED W/C RATIO	REQUIRED (Cu-Yard)
			Length	Width	Height						
WALL FOOTING	WF13	1	16-06	3-03	41-08 1/2	4000.0000	1" minus	4.0000	1.5%	0.5500	82.84
	WF13,WF14	1	16-06	5-07	4-00	4000.0000	1" minus	4.0000	1.5%	0.5500	13.64
	WF14	1	14-03	2-07	31-05 1/4	4000.0000	1" minus	4.0000	1.5%	0.5500	42.87
	WF15	1	4-00	1-02	19-07 1/2	4000.0000	1" minus	4.0000	1.5%	0.5500	3.39
	WF17	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	77.94
	WF2	2	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	26.52
	WF23	1	14-03	3-00	5-06 5/8	4000.0000	1" minus	4.0000	1.5%	0.5500	8.79
	WF27	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	29.49
	WF28	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	150.33

Total:

											435.80

CUSTOMER :

JOB NAME : THE STANDARD AT FORT COLLINS

LOCATION :

DESCRIPTION : WALL FOOTING (PARKING) NORTH BUILDING 1

DRAWING NO : RWF-01 THRU RWF-16

REVISION NO : 0

DATE :

CONCRETE REQUIREMENTS

Element Name	Part Mark	QTY.	Dimension (Ft-In)			CONCRETE PSI	AGGREGATE SIZE	REQUIRED SLUMP	REQUIRED AIR	REQUIRED W/C RATIO	REQUIRED (Cu-Yard)
			Length	Width	Height						
WALL FOOTING	WF3	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	2.90
	WF5	1	19-03	3-00	55-00 3/16	4000.0000	1" minus	4.0000	1.5%	0.5500	117.67
	WF6,WF7	1	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	5.39
	WF7	1	13-00	2-03	60-09 15/16	4000.0000	1" minus	4.0000	1.5%	0.5500	65.90
	WF7,SWF1	1	13-00	4-06	4-00	4000.0000	1" minus	4.0000	1.5%	0.5500	8.67
	WF8	3	Varry	Varry	Varry	4000.0000	1" minus	4.0000	1.5%	0.5500	90.31
	WF9	1	25-00	3-00	36-00	4000.0000	1" minus	4.0000	1.5%	0.5500	100.00
	WF9,WF23	1	25-00	4-06	4-00	4000.0000	1" minus	4.0000	1.5%	0.5500	16.67

Total:

											407.48

Grand Total:

											1514.63